



## Public Sector Data Centres Best Practice Procurement of an Energy Efficient Data Centre (Case Study)

Steve Bowes-Phipps BSc (Hons) MBCS CDCDP AUH  
12 November, 2015

# Best Practice Procurement of an Energy Efficient Data Centre (Case Study)

1. About Me
2. Reduction And Re-use of Energy in Institutional Data Centres (RARE-IDC)
3. Planning Green Data Centres
4. Best Practice Solutions
5. Measuring Success



# 1 | About Me

## Steve Bowes-Phipps

- Over 25 years of operational systems management experience
- Managed data centres for over 20 years
- Worked at the University of Hertfordshire 2007 – 2014
- A member of the Data Centre Alliance Energy Efficiency group, the EU Code of Conduct for Data Centres Best Practices Committee and regular speaker on Data Centre Best Practice

## University of Hertfordshire

- UK's leading business-facing university and an exemplar in the sector
- One of the region's largest employers with over 2,650 staff and a turnover of almost £233 million
- A student community of over 27,200 including more than 2,800 students from eighty-five different countries, the University has a global network of over 175,000 alumni
- One of the top 100 universities in the world under 50 years old, according to the new Times Higher Education 100 under 50 rankings 2012
- Sector leader in environmental management - ranked top ten in the People and Planet Green League for each of the last five years



## 2 Reduction And Re-use of Energy in Institutional Data Centres (RARE-IDC)

# Reduction and Re-use of Energy in Institutional Data Centres (RARE-IDC)



Data Centre Leaders Award Winner 2010

*“Innovation in a Micro-Data Centre”*

Uptime Institute Green Enterprise IT Award™ Winner 2011

*“Innovation in a Smaller Data Centre <1000 sq ft”*



First University *Participant* of the EU Code of Conduct for Data Centres 2010

*Green ICT* Winner of Green Gown Awards 2011



- Refurbishment of one of two main 75m<sup>2</sup> Data Centres for the University
- Funding had already been allocated in order to overcome several legacy risks
- We shared many issues with other Public Sector institutions
- Sector leader in environmental management – consistently ranked in the top ten of the People and Planet Green League
- Joint Information Systems Committee (JISC) funding brought new constraints and new objectives:
  - “An exemplar of a Green Data Centre for the HE/FE Sector”
  - “A model for other institutions to follow and learn from”
  - “Meet the business need with capacity, resilience and economy for at least ten years”



## 3 | Planning Green Data Centres

- Build Business Case on return on investment (ROI) – Not Carbon savings
- Base specifications and requirements on best practice standards
- Have a contracted efficiency target
- Seek innovation (‘cutting edge’, not ‘cookie cutter’)
- Hold back a % for results (6 months to a year is normal)
- Put Estates on the project and/or on the Board
- Run everything as a project, no matter how small
- Identify your risks and mitigate them
- Log, track and resolve issues


- Engaged closely with key stakeholders
- Bolstered our skills in best practices, cutting-edge sustainable technologies and thought leadership on reducing the carbon impact of Data Centres
- Researched a wide variety of sustainable technologies & best practices
- Design & Build Contract
- Pre-Qualification Questionnaire (PQQ) helped to reduce No. of appropriate responses
- The Invitation to Tender (I.T.T)
  - Included Best Practices (EU Code of Conduct for Data Centres)
  - British & International Standards (TIA942, etc.)
  - Would now include reference to EN50600
- Interview with top 4 Suppliers
- M&E Consultant engaged to challenge designs
- Simplification of proposals for Board approval




## 4 Best Practice Solutions

# Existing Challenges

- Pillars
- Riser
- Capacity
- Contamination from work areas
- Overhead bulkhead
- Lack of under floor capacity (only 250mm)
- Legacy incorrect (and dangerous) power cabling
- Limited plant space
- Restricted external build space
- “Meet-Me” point for all network cabling
- No external walls
- No segregation of duties



# New Data Centre Design



## Room Layout

### Practice


- Hot Aisle / Cold Aisle
- Containment
- Blanking panels
- No shelf mounted equipment
- Route cables away from fans
- Raised floor
- Tile grommets
- Position of cold aisle relative to CRAH
- Dust mat

### Impact


- Separate hot and cold air streams
- Increase efficiency of CRAH / CRAC
- Reduce / remove “hot spots”
- Improve air circulation / flow
- Prevent fan failure / filter ineffectiveness

## Hot Aisle / Cold Aisle Configurations

Example Traditional Layout



RARE-IDC Layout



## Room Layout

### Practice

- Hot Aisle / Cold Aisle
- Containment
- Blanking panels
- No shelf mounted equipment
- Route cables away from fans
- Raised floor
- Tile grommets
- Position of cold aisle relative to CRAH
- Dust mat


### Impact

- Separate hot and cold air streams
- Increase efficiency of CRAH / CRAC
- Reduce / remove “hot spots”
- Improve air circulation / flow
- Prevent fan failure / filter ineffectiveness


## Blanking Panel Effectiveness

- Effect of installation of blanking panel on server air inlet temperature

2A: Without blanking panels



2B: With blanking panels



## Room Layout

### Practice

- Hot Aisle / Cold Aisle
- Containment
- Blanking panels
- No shelf mounted equipment
- Route cables away from fans
- Raised floor
- Tile grommets
- Position of cold aisle relative to CRAH
- Dust mat

### Impact

- Separate hot and cold air streams
- Increase efficiency of CRAH / CRAC
- Reduce / remove “hot spots”
- Improve air circulation / flow
- Prevent fan failure / filter ineffectiveness

## Furniture & Fittings

### Practice

- T5 Low-energy lighting
- PIR
- Colour of racks
- Provision for additional capacity but don't build it!

### Impact

- Reduce lighting requirements
- Reduced facility power cost
- Power and cool only where needed

## Electrical configuration

### Practice

- Parallel UPSs
  - On-line Interactive
  - Dual Conversion
- Multiple Power Distribution Boards (PDBs)
- Power Factor
- TNSS Filters
- Phase balancing
- Generator

### Impact

- Clean mains supply
- Redundancy of supply
- Stability of supply
- Continuity of supply

## Cooling Effectiveness

### Practice

- “free air”
  - Direct Free Air
  - Indirect Free Air
  - Direct Water Free Air
  - Indirect Water Free Air
  - Sorption cooling (absorption / adsorption)
- Variable speed fans
- Humidifiers
- Immersion cooling
- Waste heat recycling

### Impact

- Use ambient air to extract cooling
- Don't dump all waste heat into environment
- Reduced cost of cooling
- Reduced operating cost of building
- Transferral of thermal energy

## Environment

### Practice

- Dust free
- Dry bulb inlet temp of 25-26oC
- Relative humidity of target 50% +/- 20%
- Turn off unused servers / consolidation / virtualisation
- “Lights Out” – lighting only where needed and when needed
- Separate UPS plant area

### Impact

- Reduced fan/filter failure
- Reduced cost of facility
- Reduced cost of cooling
- Cooling appropriate to equipment

## Virtualisation and Consolidation

- Turned off old servers
- Consolidated & virtualised existing services
- Reduced physical footprint
- Reduced energy (and hence, Carbon) footprint
- All new apps evaluated against virtualised environment by default
- Server utilisation rates moved from 4% -> 25% (average)
- Over 3 years saved approximately £340,000 in Capital costs & £36,000/yr Operating Expenses

## Four “M”s of Data Centre Management

### Practice

- Meter
- Monitor
- Maintain
- Manage

### Impact

- Understand your Data Centre “profile”
- Reduced cost of cooling
- Improved reliability of components and infrastructure
- Early and easier diagnosis of issues leading to speedier resolutions

## Change Management (ITIL)


- The Data Centre cannot be considered a constant
- Change can wreak untold damage on efficiency and effectiveness
- Plan for change and understand the impact



## 5 | Measuring Success

<b>Energy Consumed Per Hour</b>	<b>Before:</b>	<b>After:</b>
<b>Total IT Load</b>	120kW	120kW
<b>Total Facility Load</b>	264kW	146kW
<b>Electricity used per Year</b>	2,312,640KWh	1,282,464kWh
<b>Annual Carbon Footprint</b>	1,394 Tons	773 Tons

<b>Reduction in</b>	<b>CO2 Emissions</b>	<b>Equivalent to</b>
<b>1 Year</b>	621 Tons	117 Fewer Cars
<b>5 Years</b>	3,106 Tons	586 Fewer Cars
<b>10 Years</b>	6,212 Tons	1,172 Fewer Cars




$$PUE = \frac{\text{Total Facility Power}}{\text{IT Equipment Power}}$$

# Original Energy Breakdown


- Power Usage Effectiveness (PUE) approximated at 2.2
- IT Load at 45%
- Cooling System taking up 42% of total
- Power
- Electrical usage significant at 13%

## Before Data Centre Energy Usage



- PUE down to  $1.19_{L2,MD} - 1.33_{L2,MD}$   
Target = 1.22  
Actual =  $1.25_{L2,MD}$
- IT Load increased from 45% to 80%
- Cooling usage decreased from 42% to 19%
- Facility electrical usage decreased from 13% to 1% (UPS losses, lighting, etc.)

## After Data Centre Energy Usage



- Capability of project to act as an exemplar to the wider market in relation to the issues of the smaller data centre
  - **The first University** in Europe to achieve compliance against the EU Code of Conduct for Data Centres
  - Our pathfinder project enables others to follow our success and apply the lessons we've learned along the way
  - **Refurbishment** not new Build
  - **Re-use** of some Equipment
  - **"Free Air" Cooling** for 86% of the year (based on local weather conditions)
  - Increase in capacity of 69% & a **55% reduction in the carbon footprint** of the Data Centre
  - Operational cost savings of **£186,000 per annum** (inc Carbon cost £12/Tonne CO2)
  - Using a contained Hot Aisle configuration, **waste heat is recycled** into the building's hot water supply
  - Worked with **JISC** to further EU-wide knowledge-sharing through the e-infranet project
  - Still disseminating **Best Practice** through the EU-funded EURECA project



## Thank You

Blogs: <http://blogs.herts.ac.uk/rare-ids/>  
<http://blogs.herts.ac.uk/carbs/>

PTS Consulting Group  
60 New Broad Street, London, EC2M 1JJ

[www.ptsconsulting.com](http://www.ptsconsulting.com)